

#### **RV** Tom Crean

Modern Vessel delivering Modern Science

**Fisheries Surveys** 

**Oceanographic Surveys** 

**Environmental Monitoring** 

**Seabed Mapping** 

**Deployment of Observational Infrastructures and ROV's** 

Silent Research Vessel (ICES 209) CLASS NOTATIONS: Lloyd's +100A1, UMS, Ice Class 1C FS, DP(AM)

Department of Agriculture, Food and the Marine An Roinn Talmhaíochta, Bia agus Mara









#### **RV** Tom Crean Project timeline

- Funding secured from Government to procure a modern replacement vessel in 2018
- Design tender awarded to ST design in January 2019
- Basic design completed June 2019
- Tender issued for construction of vessel in July 2019
- Contract for vessel construction awarded to ASTILLEROS ARMON in December 2019
- Equipment procurement and further detailed design work commenced January 2020
- Steel cutting commenced August 2020, Keel laid November 2020
- Vessel launched on November 19th 2021
- Vessel delivered in Vigo on 8<sup>th</sup> July 2022
- Vessel arrives in Galway on 18<sup>th</sup> July







#### Design

- Diesel electric vessel with 3 generators @ c. 3MW (Ultra low sulphur MGO/HVO)
- 52.8 m length
- Silent vessel (Ices 209)
- Accommodation for 12 crew and 14 scientists
- Endurance of 21 days
- Capability : Fisheries research , Oceanography, Hydrography, Geology, ROV surveys , Buoy Deployments.







#### **RV** Tom Crean Acoustic equipment

- Multibeams: 1 x Dual RX EM2040 (retraction unit), 1 X em2040 on drop keel
- Provision for degree EM710 on hull
- Sub bottom profiler: Knudsen 3.5/12Khz unit hull mounted
- Fisheries echosounder: EK80 , 18,38,70, 120, 200 Khz on Drop keel
- Fisheries Sonar : SU93 Long range omnidirectional
- ADCP: RDI Teledyne 45Khz Pinnacle (Drop keel), Simrad EC150 150 Khz ADCP
- **USBL:** Sonardyne Ranger 2 on retraction unit
- Net Monitoring : Marport on drop keel /FS70 headline system









#### **Construction steps**



Steel cutting July 2020



Block construction September 2020



Keel lay November 2020





# Generator set sound trials February 2021







#### Block assembly on slipway



## Hull taking shape



#### 7 bladed prop















## Hull complete October 2021





# Final dry dock before delivery







# Sea trials











# Silent vessel





# **Delivery Day!**





# Delivery and departure to Ireland















#### Activities since delivery

#### INFOMAR PROGRAMME



Self: 1:200
 Self: 1

1<sup>ST</sup> Survey 25<sup>th</sup> July 15 day
seabed mapping survey as part
of INFOMAR program
1000km2 of Celtic sea mapped.

Some teething issues with SIS Version 5, but vessel performing excellently with no bubbles and excellent acoustic performance

Experienced Marine Institute team essential to get to grips with new systems







### Activities since delivery UWTV survey

- Following a week of crew familiarisation/Training the Annual Porcupine bank Prawn Underwater TV survey was completed
- Vessel generally performed well with much higher weather window for operation compared to Celtic Voyager
- Sonardyne ranger 2 performing very well in tows to c. 700m water depth, speed restriction on USBL when fully deployed
- A frame working well and excellent visibility from Bridge







#### Activities since delivery... Oceanographic survey

- Short 6 day shelf Oceanographic survey (Harmful algal blooms)
- Good trial for CTD system
- Active Heave taking some getting used too
- Potential modification identified to CTD Docking head to prevent wire wear
- Automated deployment and recovery working well
- Underway systems (SooGuard) up and running







### Current survey Meso pelagic scouting survey

Survey to determine temporal and spatial distribution of meso pelagic species

Equipment in use:

- EK80
- Pelagic trawl
- CTD
- Multinet
- SU 92

12 day survey with full crew underway

at present Challenging survey with Fishing, acoustics, CTD (1000m), Multinet but a good trial of many systems







# Busy Schedule for remainder of 2022





# Challenges /lessons learned

- Difficult to take over a new vessel while operating old vessel! (Celtic Voyager finished operations on 12/07/2022 and Tom Crean sailed for Ireland on 15/07!) This limited time for training/ crew familiarisation
- As a result training is very much " on the job" at present
- More time for sea trials preferred A lot of pressure to commence work program when vessel in service
- More time to be allowed for crew training / addressing minor issues
- Flag state had very severe interpretation of MLC standards e.g. No exemption for vessels below 3000gt and MLC applied fully from 500GT
- Some owner supplied science equipment, challenging for owner and yard as commissioning responsibilities lie with different owners so a lot of management of suppliers
- Single cabins only for future vessel !







# Challenges /lessons learned

- Fuel consumption seems very good and power management system is excellent,
- Harbour set proving its worth (750 -800 L/24hrs) and creates quiet engine room
- Awaiting suitable port with connection to use Shore power
- Energy efficiency review of design has resulted in excellent HVAC/water heating and low hotel loads
- Scientists and crew very happy with the vessel, light, spacious, good sea keeping
- Winch system very advanced so some training for scientists required also
- Owner supplied KVM system /Network too a lot off effort and time to commission
- Experienced crew help make new vessel transition easier but its still a pressurised time with a full survey schedule to complete ....

