

MSRV – Mid-Shore Research Vessel

NSH – Navire Semi-Hauturier

Victor MARTIN – Naval Engineer

June 2024



www.flotteoceanographique.fr

La Flotte océanographique française,
une très grande infrastructure de recherche opérée par l'Ifremer



AGENDA

1. General Vessel Specs
2. Innovative Electrical System
3. Detailed Specs of the Vessel
4. Vessel Operational Scenarios
5. Project Org., Schedule & Progress
6. Challenges

1 – Generalities

Characteristics of the future vessel

Length :
45 m

Breadth :
11,5 m

Draught max :
4,3 m
(incl. gondola)

Accommodation

22 people

- 12 crew
- 10 scientist

19 days of
autonomy

At least 30% less environmental impact than a
standard-built vessel

“Low consumption” and “silent” ship




Missions Missions to be carried out:

- Physico-biogeochemical campaigns
- Campaigns on biology, ecosystem ecology and fishing technologies
- Underwater research campaigns
- Ecosystem campaigns

2 – Innovative Electrical System

Energy production & distribution system

- Decision for **1000V DC power bus** on board :
 - Variable speed AC Gensets, always use engines at optimal speed for the required load
 - No reactive power on DC / no associated power loss.
 - Easier integration of other power sources (Batteries / solar / wind /...)
- LFP Battery pack of 740 kWh :
 - Ensuring power supply in port, if no quayside supply
 - Power Back-up in case of Genset black-out
 - 1.5h of vessel activity on DP or towing equipment at low speeds (2 to 4kts)



3 – Detailed Specs of the Vessel

General fittings :

Rooms	Target area
Mission control room	20,5 m ²
Laboratories (wet and dry)	63 m ²
Technical spaces	40 m ²
Main deck	110 m ²
Electronic workshop	12 m ²
LEI	12.5 m ²
Mess	28 m ²
Galley	16 m ²
Cabins	- 6 simples - 1 simple/double - 8 doubles

3 – Detailed Specs of the Vessel

Scientific Equipment

Equipments on keel or gondola	
Kongsberg EK80 Sounders	18, 38, 70, 120, 200 & 333 kHz
Multi beam echo sounders	EM712 0,5° x 1°
Sub bottom profiler	IxBlue T3
ADCP	75, 300 & 600 kHz
Fishery trawl and net monitoring device	Marport equipment
Ultra short baseline (USBL) positioning device	GAPS (mobile equipment)
Several	Acoustic remote control TT-8011 Pinger EA440 Loch Doppler

3 – Detailed Specs of the Vessel


Scientific Equipment

Mobile equipment

Continuous measurements	Thermosalinometer SBE21 + SBE38 Ferry-Box sensors installed on THSM SW-line, with in-house data storage automation.
CTD	SBE11 – SBE19 + deck unit
Underwater vehicles	AUV Asterix ou Idefix HROV Ariane Ulyx
Sismic equipment	Ifremer mobile equipment
Coring equipment	10 m Calypso – Up to 2000m, cable diam 18 mm Vibro-carottier – Thomas Schmidt Type de Geo Marine Survey « 3m »
Various	LARS ROV


3 – Detailed Specs of the Vessel

General Arrangement – Rev 6



3 – Detailed Specs of the Vessel

General Arrangement – Rev 6



3 – Detailed Specs of the Vessel

New Renderings



4 – Vessel Operational Scenarios

Physico-biogeochemic campaign







Illustration of S1 – 2D Views of Scenario cases


4 – Vessel Operational Scenarios

Underwater vehicles principles




4 – Vessel Operational Scenarios

Underwater vehicles principles



4 – Vessel Operational Scenarios

Underwater vehicles principles



4 – Vessel Operational Scenarios

Fishery campaign





Illustration of S4 deck configuration - Iso view

4 – Vessel Operational Scenarios

Fishery campaign



4 – Vessel Operational Scenarios

Geoscientific





Illustration of gravity corer deck configuration – Iso view

Illustration of light seismic deck configuration – Iso view

4 – Vessel Operational Scenarios

Geoscientific campaign





Illustration of gravity corer deck configuration – Iso view

Illustration of light seismic deck configuration – Iso view

4 – Vessel Operational Scenarios

Paleoclimatic campaign




Illustration of gravity corer deck configuration – Iso view





Illustration of light seismic deck configuration – Iso view

5 – Project Org. Schedule & Progress

- Signature of EPC contract : 10 May 2023 with **CONSTRUCCIONES NAVALES P. FREIRE S.A. at Vigo.**
- Design process well-advanced, Steel Structure almost frozen
- Steel Cutting of the first sheet : 24th of April 2024
- Keel Laying : 12th of July 2024
- Launching : February 2025
- Delivery : End of 2025 – After Shipyard trials
- Scientific trials : 3 months – Q1 of 2026
- Fleet entry: Q2 of 2026

5 – Project Org. Schedule & Progress

General organization with main stakeholders.



- XXXXXX : Deck Machinery
- XXXXX: Electrical System & Mgmt
- XXXXXXXX : Electrical Installation
- XXXXX : Propulsion
-

6 - Challenges


Past Challenges :

- Hull shapes design for vessel stability
- Hull & Gondola shapes / positioning for optimized Bubble sweep-down.

Complete Vessel shapes redesign after Tank tests in Oct-2023.

Vessel Bow extended (Loa = 40 -> 45m), vessel breadth increased (10,2 -> 11,5m).

6 months of project delays for complete re-engineering done in-house at the shipyard.



6 - Challenges

Upcoming Challenges :

- Management of Batteries on board (storage, safety, etc)
- Implementation of a DC high-voltage bus (1000V) for all main power consumers.

Thank you for your attention